LiftWatch

Platform explained: what it does, how it works, the method, and open questions

Pilot version · method LW-M1.1 · built 23 October 2026

What LiftWatch is. A mobile web app that helps an Appointed Person (AP) check a planned crane lift against the wind forecast, run the other pre-lift checks, and record a decision. It is **decision support, never an authorisation to lift**. The crane operator always has the final say.

Why this document exists. It is a complete, self-contained description of the platform for use with other AI tools for further research. Every formula, number, rule and assumption is written out, with its source. Section 15 lists open research questions, and section 16 gives ready-made prompts. Where something is a LiftWatch choice rather than a rule from a standard, it says so.

"LiftWatch" is a working name. Live pilot: https://liftwatch.pages.dev (method page: /method). Code: the `liftwatch/` folder of a private GitHub repository.

Contents

1. Summary
2. The problem it addresses
3. Who uses it
4. Scope of the pilot
5. How it works: the screens
6. The wind method in full
7. Load schedule
8. The other checks
9. Lift-day wind log
10. Records, PDFs and audit
11. Data sources
12. Architecture and technology
13. Design and wording rules
14. Limitations and assumptions
15. Open research questions
16. Prompts for other AI tools
17. Glossary and references

1. Summary

Item	Detail
Purpose	Check a planned crane lift against the wind forecast and other pre-lift checks, and record the Appointed Person's decision with a full audit trail.
Users	Appointed Person (AP) and lift supervisor on UK construction sites; crane operator and slinger/signaller see the briefing and wind log.
Pilot scenario	Timber frame wall panels, floor cassettes and similar flat loads, lifted by a mobile crane on a UK site.
Status	Working pilot, deployed on Cloudflare Pages, with an automated test suite. Not yet reviewed by a qualified AP.
Main outputs	A status per hour (Within limits / Near limit / Over limit), a permitted wind speed for each load, checks results, a read-only decision record, a full PDF, a one-page crew briefing sheet, and a lift-day wind log.
Key sources	CPA/TCIG 2507 "Planning and Control of Lifting Operations in Wind" (July 2025); BS EN 13000; BS 7121-1; EN 1991-1-4; LOLER 1998; LEEA guidance; Open-Meteo forecasts; postcodes.io.
Technology	Vite + TypeScript (no framework), jsPDF, Vitest; IndexedDB on the device; optional Cloudflare Worker as a forecast cache; works offline.
Not included	Logins, sharing between people, billing, alerts, lightning data, a crane library.

2. The problem it addresses

In the UK, every lifting operation must be planned by a competent person, supervised and carried out safely (LOLER 1998). BS 7121 is the code of practice, and the planner is called the Appointed Person. Wind is one of the hardest parts of a lift plan, and large light loads such as timber frame panels are the most sensitive to it.

Why wind planning goes wrong

- Forecasts give wind at 10 m above ground, often as a 10-minute mean, for the middle of a grid square. The crane's limit is a 3-second gust at the jib head (CPA pages 20–21).
- Crane load charts assume a load with 1.2 m² of effective wind area per tonne. A big light panel has far more, so its permitted wind speed is lower than the chart limit. The CPA guide notes that APs "struggle to understand the shape-factor assessment" (section 4.4).
- Wind increases with height, and by how much depends on the terrain (open country, towns, cities).
- Anemometers and forecasts use different units: m/s, mph, km/h and knots.

Other common reasons lift plans fail review

From industry guidance and lift-plan reviewers (practitioner evidence, not formal studies):

- Capacity not checked against the crane's actual configuration; lifting accessories and hook block left out.
- Load weights assumed rather than confirmed.
- Ground bearing pressure under outriggers assumed rather than calculated.
- Sling angles and ratings wrong.
- Exclusion zones drawn round the crane instead of the load's swept path; overhead power lines missed.
- Lifting accessories past their 6-month thorough examination.
- Briefings not done or not recorded; stops and restarts in wind not recorded.
- Changes on the day made informally instead of re-planning.

The CPA guide also notes that more lifting time is lost to poor use of load bays and site logistics than to winding off, and recommends doing wind-sensitive lifts in calmer hours (section 4.4, page 22).

3. Who uses it

Role	What they do in LiftWatch
Appointed Person (AP)	Enters the lift, reads the assessment, completes the checks, records the decision (Proceed / Postpone / Proceed with conditions).
Lift supervisor	Runs the briefing and crew sign-on, keeps the wind log on the day.
Crane operator	Has the final decision to lift, continue or stop (CPA 6.4). Reads the briefing sheet; their anemometer readings go into the wind log.
Slinger / signaller	Signs on to the briefing.
Principal contractor / client	Receives the PDF record. (Approval inside the app is not built yet.)

4. Scope of the pilot

In scope	Out of scope (for now)
UK sites; timber frame panels, cassettes and similar flat loads; mobile crane; forecasts up to 7 days; one or many loads per plan; checks for capacity, slings, ground bearing, examinations, cards; decision records on the phone; PDFs; offline use.	Logins and accounts; sharing and approval between people; billing; alerts; lightning feeds; a crane library or manufacturer data; tower cranes (method not designed for them); tandem lifts; lifting people; drawing a site plan.

5. How it works: the screens

Five tabs along the bottom of the phone screen: Set-up, Assessment, Checks, Decision, Records. Inputs are saved on the phone as you type.

5.1 Set-up

- **Site:** UK postcode (looked up with postcodes.io) or latitude/longitude.
- **Terrain:** open country, town or city (changes how much the gust rises with height).
- **Lift:** date (today to 6 days ahead), optional planned start and finish time, crane description.
- **Crane wind limit:** the in-service limit from the load chart in m/s, **where that figure came from** (required, e.g. “Lift plan LP-014 / LTM 1090 load chart”), whether it is a gust or a mean, and the boom / jib head height (up to 150 m).
- **Main load:** reference, length and height of the face presented to the wind, mass, rigging mass (slings, hook block and hoist rope), drag coefficient cw (default 1.2).
- **Other loads (optional):** typed in, or pasted from a supplier’s panel schedule.
- **Working:** the permitted wind speed and every step of the calculation update as you type, plus the gust factor at height, the “near limit” threshold, and the same limit expressed as a 10 m forecast gust.

5.2 Assessment

- Fetches the 7-day forecast for the site and works out each hour of the lift day.
- **Status banner** with only this wording: “Within limits / Near limit / Over limit — forecast assessment against the limits you entered”. It shows the worst hour in the lift window.
- Gust at height vs permitted speed, % of the limit, wind direction, weather flags.
- The forecast source, model and fetch time, always shown.
- An hourly bar chart (gust at height against a dashed permitted line, night shaded) and an hour-by-hour table.

- With several loads: the governing (most wind-sensitive) load, and a table of which loads are within limits in each daylight hour.
- “Planning guidance only”: daylight periods of 2+ hours within limits. “Outlook — planning guidance only”: a 7-day strip; tap a day to assess it.

5.3 Checks

Crane capacity, slings, outrigger ground bearing, thorough examination dates, competence card expiry, a 14-item pre-lift checklist and crew briefing sign-on. A summary shows how many items need attention and how many are not done. Nothing here blocks a decision. Details in section 8.

5.4 Decision

- Shows the status, the worst hour and a summary of the checks.
- The AP chooses Proceed, Postpone or Proceed with conditions, and enters name, role and notes (conditions are required for “Proceed with conditions”).
- Two confirmations, required for either kind of Proceed: “I have checked on-site wind with an anemometer or the crane’s jib anemometer before lifting” and “The crane operator retains the final decision to lift, continue or stop”.
- Saving creates a timestamped, read-only record (section 10).

5.5 Records

- List of saved records on this phone; view any record in full.
- **PDF**: the full record. **Briefing sheet**: one page for the crew and the cab.
- **Wind log on the day** (section 9).
- **Use as new set-up**: start a new lift from a saved one.
- Export all records and wind logs as JSON; import them on another phone.

6. The wind method in full

Method version LW-M1.1, stored in every record. The code that applies it is a pure module with no screen or network code (`src/wind/`), and every formula carries its source in a comment.

6.1 Step 1: the 10 m gust corrected to boom / jib head height

Open-Meteo provides the gust at 10 m. It is multiplied by a height factor F(h). For open country, LiftWatch uses the Liebherr factors quoted in the CPA guide (page 21):

Height (m)	10	50	100	150
Gust factor F	1.000	1.181	1.272	1.329

Between table points, F is interpolated linearly in log(height):

```
t    = ln(h / h_lo) / ln(h_hi / h_lo)
F(h) = F_lo + t × (F_hi − F_lo)
gust at height = gust at 10 m × F(h)
```

- Below 10 m: F = 1.0 (no reduction).
- Above 150 m: refused, “outside method range”.
- Example: at 25 m, F = 1.103; at 30 m, F = 1.124.

6.2 Terrain: open country, town or city

Wind near the ground is slowed more by rough terrain, so the gust rises more with height in towns and cities (CPA section 5.2 and Annex H). Town and city use the gust (peak velocity) profile of EN 1991-1-4, as a ratio to the gust at 10 m. The basic wind speed cancels out:

```
vm(z) ∝ ln(z / z0)                  mean wind, flat terrain
```

```
Iv(z) = 1 / ln(z / z0)              turbulence intensity
vp(z) = vm(z) × √(1 + 7 × Iv(z))    peak (gust) speed
F(h)  = vp(max(h, zmin)) / vp(max(10, zmin))
```

Setting	Meaning	EN 1991-1-4 category	z0 (m)	zmin (m)
Open country	Fields, coast, airfields, scattered buildings	II	0.05	2
Town	Suburbs, villages, industrial estates, woodland	III	0.3	5
City	City centre, ≥ 15 % covered by buildings over 15 m	IV	1.0	10

Open country keeps the published Liebherr factors because the EN 1991-1-4 category II profile gives 1.214 / 1.305 / 1.358 at 50 / 100 / 150 m, within 3 % of them. Town and city are never below the open-country factor.

Height	Open country	Town	City
20 m	1.078	1.130	1.182
30 m	1.124	1.204	1.285
50 m	1.181	1.297	1.412
100 m	1.272	1.421	1.580
150 m	1.329	1.493	1.676

6.3 Step 2: 10-minute mean to gust (for future sources)

If a source gives only a 10-minute mean at 10 m, CPA page 21 gives factors to a gust at height: 50 m 1.653, 100 m 1.78, 150 m 1.861, interpolated the same way. Below 50 m a 10 m factor must be entered (there is no published value, so the method refuses without one). Built and tested, but not used in the pilot because Open-Meteo provides gusts.

6.4 Step 3: permitted wind speed for the load (wind-area reduction)

Source: BS EN 13000 assumption (load charts assume 1.0 m² per tonne with cw 1.2, i.e. 1.2 m² of effective wind area per tonne); formula as CPA section 4.3 and Annex A, from the Liebherr wind document; BS 7121-1:2016 Annex D-1 sets out the same assessment as a flow chart.

```
Ap = length × height                    projected area (m²)
Aw = Ap × cw                            effective wind area (m²)
m  = (load mass + rigging mass) / 1000  total mass (t)
r  = Aw / m                             ratio (m²/t)
r0 = 1.2 m²/t
if r ≤ r0:  permitted = chart limit
if r > r0:  permitted = chart limit × √(r0 / r)   (never above the chart limit)
```

Why the square root: wind force is proportional to v² × Aw. Holding the force at the chart's design value gives v_perm² × Aw = v_chart² × r0 × m.

Worked example (LiftWatch's own): panel 3.6 × 2.4 m, cw 1.2, 1,300 kg, chart limit 17 m/s → Ap 8.64 m², Aw 10.368 m², r 7.975 m²/t, permitted 17 × √(1.2 / 7.975) = **6.59 m/s** (14.8 mph).

Checked against the CPA guide's own worked examples (automated tests):

CPA example	Guide	LiftWatch
Annex E Fig 15: shutter 2.4 × 6.6 m, 2.392 t, mobile crane 11 m/s	4.3	4.27
Annex E Fig 15: shutter 7.2 × 6.6 m, 7.215 t, mobile crane 11 m/s	4.3	4.29
Annex E Fig 15: pack of ply 2.4 × 0.7 m, 0.9 t, mobile crane 11 m/s	8.1	8.05
Annex E Fig 15: person basket 1.45 × 1.1 m, 0.64 t, mobile crane 11 m/s	7.0	6.97
Annex E Fig 14: shutter 2.4 × 6.6 m, 2.392 t, tower crane 17 m/s	6.6	6.61

CPA example	Guide	LiftWatch
Annex E Fig 14: pack of ply 2.4 × 0.7 m, 0.9 t, tower crane 17 m/s	12.4	12.44
Section 4.3: insulation pack 1.2 × 2.4 m, 113 kg, 11.1 m/s	2.1	2.20

The insulation pack is the one difference: the guide prints 11.1 × 0.198 = 2.1, but the product is 2.198. The guide's own "80 % reduction" matches 2.2, so the printed 2.1 appears to be a rounding slip.

6.5 The chart limit must be a gust

EN 13000 applies a 3-second gust to the crane at height, and CPA says decisions use gusts, not means (section 3.3). If the AP says the chart limit is a 10-minute mean, LiftWatch does not assess and asks for the gust figure.

6.6 Step 4: hourly status

```
ratio = gust at height / permitted wind speed
```

Ratio	Status
below 0.80	Within limits
0.80 to 1.00 inclusive	Near limit
above 1.00	Over limit
gust missing	No data (never a pass)

The 0.80 band is a LiftWatch pilot choice, not from CPA or any standard. The percentage shown never contradicts the status: near a threshold it shows one decimal place, or "< 80 %" / "> 100 %".

6.7 Weather flags (LiftWatch choices; never a pass)

Flag	Rule (Open-Meteo variable)
Thunderstorm risk	CAPE above 500 J/kg
Possible thunder	CAPE 100–500 J/kg
Visibility below 5 km	visibility under 5,000 m
Rain likely	precipitation probability ≥ 70 %
Frost / ice risk	temperature ≤ 1 °C
Outside daylight	hour starts before sunrise or at/after sunset
Data missing	any value used for a flag is missing

6.8 Lift window, planning periods and outlook

- Lift window: the AP's planned start–finish, or sunrise to sunset. The banner shows the worst hour in it (ranked Over limit, No data, Near limit, Within limits; then highest ratio).
- Planning periods: runs of 2+ consecutive daylight hours within limits, clipped to sunset.
- 7-day outlook: per day, the worst daylight status and the highest gust at height.

6.9 Units

m/s first, mph second. 1 mph = 0.44704 m/s; 1 km/h = 1/3.6 m/s; 1 knot = 1852/3600 m/s.

7. Load schedule

A timber frame day is many panels, not one load. Other loads can be typed in or pasted from a supplier's panel schedule: rows of reference, length (m), height (m), mass (kg, or tonnes with "t"), and optionally rigging (kg) and cw, separated by tabs, commas or semicolons. A header row is skipped; bad rows are reported by line number.

- Each load gets its own permitted speed (section 6.4).

- Every load sees the same gust, so the load with the lowest permitted speed is the worst in every hour. That **governing** load sets the banner and the record's headline figures.
- A table shows, for each daylight hour, which loads are within limits (✓ within, ! near, × over), most wind-sensitive first, with each load's within-limit windows. This supports CPA's advice to lift light, large loads in calm hours and heavy, compact ones in windier hours (page 22).

8. The other checks

These sit beside the wind method. They are saved in the decision record and printed in the PDF, but they never change the wind status and never block a decision.

Check	Rule	Source / status
Crane capacity	hook load = load + accessories + hook block and rope; utilisation = hook load ÷ rated capacity from the chart at the planned radius. Flagged above 75 % (justify in plan) and 90 % (high); over 100 % is over the chart.	Hook load as CPA Annex A. The 75 % / 90 % bands are company-rule settings, not legal limits.
Slings	Leg angle β = asin(d ÷ leg length); d = half the spacing (2 legs), half the diagonal (4 legs), spacing ÷ √3 (3 legs). Mode factor: 2 legs 1.4 (β ≤ 45°), 1.0 (≤ 60°); 3–4 legs 2.1, 1.5; over 60° not permitted. Required single-leg WLL = load ÷ factor.	Uniform load method: BS EN 818-4, BS EN 13414-1, BS EN 1492-1; LEEA Code of Practice.
Outrigger ground bearing	pressure = (outrigger load + mat weight) ÷ mat area, in kN/m² (tonnes × 9.81); compared with the allowable pressure; minimum mat area = load ÷ allowable.	Simple uniform-pressure check; assumes a stiff mat. Outrigger load from the manufacturer, allowable pressure from the ground assessment (CPA Ground conditions for construction plant, 2014).
Thorough examinations	Crane in date if the lift date is within 12 months of its last examination; lifting accessories within 6 months.	LOLER 1998 regulation 9 (a written scheme can set other intervals).
Competence cards	Operator, slinger/signaller and lift supervisor: card scheme and number, valid if the expiry is on or after the lift date.	—
Crew sign-on	Names, roles and sign-on times after the briefing.	CPA 6.1.3: brief the permissible wind speed to the team.

The 14-item pre-lift checklist (Yes / No / N/A)

1. Load weights confirmed from drawings, schedules or weighing, not estimated
2. Lifting points or panel lifting brackets are as designed and inspected
3. Ground and outrigger set-up as the plan: mats, full extension, level
4. Underground services, voids and excavations near the outriggers checked
5. Overhead power lines identified and controls in place
6. Exclusion zone set out around the load path and slew, not only the crane
7. Public, roads and neighbours protected where loads pass over or near
8. Crane anemometer working and reading 3-second gusts
9. Radio channel and signals agreed, with a back-up
10. Taglines or other load control available and briefed
11. Temporary bracing or propping ready for placed panels
12. Lighting adequate if lifting outside daylight
13. Emergency and rescue arrangements agreed
14. Lift plan briefed to the whole lifting team

9. Lift-day wind log

Opened from a saved record. Readings from the crane's anemometer (a gust at the boom / jib head) are entered in m/s, mph, km/h or knots and compared directly with the governing load's permitted speed. No height factor is applied, because the anemometer is already at height. The pattern follows CPA section 6.4.3.

State	When
Within limit	the last reading is below 80 % of the permitted speed
Near limit	the last reading is 80 % to 100 % of it
Stop	a reading is above the permitted speed
Waiting	after a stop, readings are back at or below the limit; the wait runs from the first such reading
Wait complete	readings have stayed below the limit for the wait time (default 30 minutes per CPA 6.4.3; 10 or 20 selectable; BS 7121-5 uses 10 for tower cranes). The crane operator decides whether to restart.
Winded off	logged as winded off for the day

- A reading above the limit while waiting resets the wait. After three resets the log quotes CPA 6.4.3: the day may need to be declared winded off.
- It shows which loads in the schedule are still within their own limit at the last reading.
- For information only, each reading is compared with the forecast gust at height for that hour, and the average measured ÷ forecast ratio is shown (CPA 5.2.2: contractors are trialling forecast correction from site readings).
- Entries are append-only (no edit or delete), with time and optional name, and are printed in the PDF.
- The log never says a lift may go ahead.

10. Records, PDFs and audit

What a decision record holds

- Every input (site, terrain, date, window, crane, chart limit and its source, limit type, height, all loads).
- The full calculation for every load, the height factor and the hourly assessment for the lift day.
- The raw forecast values used for the lift day, the forecast source, endpoint, model, grid point and fetch time.
- The decision, name, role, notes and the two confirmations.
- The checks with every result worked out.
- The method version, the app name, a timestamp, and a SHA-256 hash of the whole record.

Records are frozen when saved and can never be edited. The hash detects any later change: an edited record is flagged on screen, in the PDF, and rejected on import.

PDF outputs

Output	Contents
Full record PDF	Status, decision, lift, calculation, loads table, forecast details, hourly chart and table, planning guidance, checks, wind log, method summary, sources, integrity hash, and the disclaimer footer on every page.
Briefing sheet (1 page)	Stop reading for every load in m/s, mph, km/h and knots; the restart rule; the operator's final say; lift window and flags; checks needing attention; crew names and blank signature lines.

Footer on every PDF: “Forecasts are modelled estimates, not measurements. This assessment supports, and does not replace, the lift plan, the Appointed Person’s judgement, manufacturer data, BS 7121 and on-site wind checks.”

11. Data sources

Forecast: Open-Meteo

```
hourly = wind_speed_10m, wind_gusts_10m, wind_direction_10m, wind_speed_80m,
         wind_speed_120m, cape, precipitation_probability, visibility, temperature_2m
daily  = sunrise, sunset
wind_speed_unit=ms  timezone=Europe/London  forecast_days=7
```

- Model: Open-Meteo’s “best match” blend for the location. The response does not say which model run was used, so LiftWatch records the time it fetched the forecast.
- The free endpoint is for non-commercial use; a commercial endpoint and API key are configurable.
- Wind speed units are checked on every response, so a configuration slip cannot mix km/h into m/s.
- Coordinates are rounded to 2 decimal places (about 1 km). An optional Cloudflare Worker caches each site’s forecast for 60 minutes so many users share one call; the pilot currently calls Open-Meteo directly.

Location: postcodes.io

Free UK postcode lookup to latitude/longitude. Latitude/longitude can also be entered by hand. Only UK and Ireland coordinates are accepted.

12. Architecture and technology

Part	Detail
Front end	Vite 8 + TypeScript, no framework, mobile-first. Five screens, an SVG hourly chart, a method page built from METHOD.md.
Pure logic	`src/wind` (wind maths), `src/checks` (capacity, slings, bearing, dates, checklist), `src/windlog` (stop/wait/reset), `src/lift` (set-up, assessment, records). No screen or network code.
Data	`src/data`: Open-Meteo request and parsing (shared with the Worker), postcode lookup, offline forecast copy.
Storage	IndexedDB on the phone (records and wind log), behind an append-only RecordStore interface (list, get, add, addLogEntry, listLog) so it can move to Supabase. Drafts in localStorage.
PDFs	jsPDF in the browser, loaded on demand.
Offline	A service worker keeps the app and PDF library on the phone. The last forecast per site (up to 48 h old) is used with no signal, with a clear warning and its fetch time.
Server	Optional Cloudflare Worker: forecast proxy with 60-minute cache. No other server.
Hosting	Cloudflare Pages (liftwatch.pages.dev), built from the repository on every push.
Tests	Vitest (npm test): CPA worked examples, factors, terrain, thresholds, invalid inputs, parsing, Worker, records and integrity, export/import, checks, wind log, PDFs. Plus scripted browser runs.
Dependencies	Vite, TypeScript, Vitest, jsPDF only.

13. Design and wording rules

- The status banner uses only “Within limits / Near limit / Over limit — forecast assessment against the limits you entered”. Never “safe”, “clear to lift” or “go”.
- Status is never shown by colour alone: always an icon and a text label (green / amber / red).

- Weather flags never count as a pass. Missing data never counts as a pass.
- High contrast for bright daylight; large tap targets for gloves; light and dark themes; works one-handed.
- The forecast source and fetch time are always shown.
- The AP decides; nothing blocks a decision; the crane operator has the final say on the day.

14. Limitations and assumptions

Known limitations

- **Forecast resolution:** a modelled forecast on a grid; it does not resolve the crane position.
- **Local funnelling** between buildings, around structures and over ridges is not modelled.
- **Terrain** is a three-way choice with flat-terrain profiles; hills and the UK National Annex's detailed procedure are not used.
- **Single scenario:** flat loads, mobile crane, gust-based chart limit, up to 150 m.
- **Records on the device only:** lost if site data is cleared or the phone is lost; export regularly.
- **Open-Meteo free tier** is non-commercial.
- **Checks are simple calculations:** capacity uses the chart figure entered; the sling check assumes a centred hook and equal legs; the bearing check assumes a stiff mat.
- **Not yet reviewed by a qualified Appointed Person.**

LiftWatch choices that need an AP's review

Choice	Default	Basis
Near limit band	80 % of permitted	Pilot choice
Capacity bands	75 % and 90 %	Common contractor practice (not a standard)
Weather flag thresholds	Section 6.7	Pilot choice
Restart wait	30 minutes	CPA 6.4.3 "common practice"; 10 and 20 selectable
Checklist items	14 items	Common review failings, CPA, STA
Terrain mapping	II / III / IV	EN 1991-1-4 Table 4.1

15. Open research questions

Questions this pilot has not settled. Each is worth researching with other sources or tools.

Method and standards

1. What exactly does BS 7121-1:2016 Annex D-1 say, and does LiftWatch's wind-area reduction match it word for word?
2. What roughness or terrain do the Liebherr gust factors (1.181 / 1.272 / 1.329) assume?
3. How does the UK National Annex to EN 1991-1-4 treat town and city terrain, and how different would its factors be from LiftWatch's town/city values?
4. Open-Meteo describes its 10 m gust as the maximum gust over the preceding hour (to be confirmed). Is that comparable with a crane anemometer's 3-second gust, and should a correction be applied?
5. Which weather model drives Open-Meteo's "best match" for UK sites, and how accurate are its gust forecasts at 1–3 days?
6. What are the BS 7121 lift categories (basic / intermediate / complex) and their criteria?
7. Is 80 % a sensible "Near limit" band? What do contractors and crane hirers use?
8. Are the 75 % / 90 % capacity bands typical of UK principal contractors' lifting procedures?

9. What do manufacturers (Liebherr, Tadano, Grove) say about wind on panels, and do any give load-specific charts?

Product and market

1. Which tools do UK APs and timber frame erectors use today for lift planning and wind (e.g. Crane Team, LiftPlanProUK, Liebherr Crane Planner, 3D Lift Plan), and what gaps do users report?
2. What would principal contractors need before accepting LiftWatch records as part of lift plan approval?
3. How should multi-person approval (AP → principal contractor → client) work, and what audit evidence is needed?
4. Which crane makes expose anemometer data through telemetry APIs, and on what terms?
5. What would a fair pricing model be for contractors and timber frame suppliers?

Legal, liability and data

1. How should decision-support software be worded and contracted so it is not taken as authorising a lift?
2. What are the UK GDPR implications of storing names, roles and sign-on times of the lifting team?
3. What record retention is expected for lift plans and wind decisions after an incident?

Validation

1. How should a pilot be designed to compare forecast gusts at height with crane anemometer readings, and how many lift days would give useful evidence?
2. Which incidents or near misses involving wind and large-area loads are documented in the UK (HSE, CPA, CIRAS)?

16. Prompts for other AI tools

Attach this PDF, then paste one of these:

Prompt 1. You are an experienced UK Appointed Person (CPCS A61) and lift supervisor. Review the LiftWatch method in sections 6–9 of the attached document. List anything that is wrong, unsafe, or not in line with BS 7121, LOLER or the CPA wind guide, with references.

Prompt 2. Check every formula and number in section 6 of the attached document against BS EN 13000, BS 7121-1 Annex D and the CPA/TCIG 2507 guide. Recompute the worked examples and report any differences.

Prompt 3. Research the open questions in section 15 of the attached document. For each, give an answer with sources, and say how confident you are.

Prompt 4. Act as a product manager for UK construction software. Using the attached document, list the next five features that would most help UK timber frame erectors and principal contractors, with reasons and evidence.

Prompt 5. Compare LiftWatch (attached) with existing UK lift-planning tools. What does each do that LiftWatch does not, and where is LiftWatch different?

Prompt 6. As a UK construction lawyer, review how LiftWatch (attached) describes itself and records decisions. What wording, terms of use and data protection steps does it need before commercial use?

Prompt 7. Design a 3-month pilot study for LiftWatch (attached) on timber frame sites: what to measure, how many sites and lift days, and how to judge whether the forecast assessment is reliable.

17. Glossary and references

Term	Meaning
AP	Appointed Person: the competent person who plans the lifting operation (BS 7121).
Lift supervisor	Supervises the lift on site in line with the plan.
Chart limit	The crane's in-service wind limit for its configuration, from the manufacturer's load chart (a 3-second gust at the jib head).
Permitted wind speed	The limit for a particular load after the wind-area reduction.
Gust at height	Forecast 10 m gust × height factor: the estimated gust at the boom / jib head.
cw	Drag (shape) coefficient: 1.2 for flat panels by default.
Ap, Aw	Projected area of the face to the wind; effective wind area (Ap × cw).
Governing load	The most wind-sensitive load in a plan (lowest permitted speed).
WLL	Working load limit of a sling or accessory.
Mode factor	Multiplier for a multi-leg sling's WLL by number of legs and angle (uniform load method).
CAPE	Convective available potential energy: an indicator of thunderstorm potential.
LOLER	Lifting Operations and Lifting Equipment Regulations 1998.
GS6	HSE guidance: Avoiding danger from overhead power lines.

References

- CPA/TCIG 2507, Planning and Control of Lifting Operations in Wind, V1, July 2025.
- BS EN 13000:2010+A1:2014, Cranes. Mobile cranes.
- BS 7121-1:2016, Code of practice for safe use of cranes. General (Annex D-1).
- BS EN 1991-1-4, Eurocode 1: Actions on structures. Wind actions (Table 4.1; clauses 4.3–4.5).
- Liebherr, Wind influences on cranes (2017).
- LOLER 1998, regulation 9; HSE, Thorough examination of lifting equipment.
- LEEA Code of Practice for the Safe Use of Lifting Equipment (rating for modes of use).
- BS EN 818-4, BS EN 13414-1, BS EN 1492-1 (sling ratings).
- CPA, Ground conditions for construction plant (2014).
- HSE GS6, Avoiding danger from overhead power lines.
- Structural Timber Association, Health and Safety Code of Practice.
- Open-Meteo forecast API (open-meteo.com); postcodes.io.